



**CONSTRUCTION NOTES:**

1. ADD NEW RAMP, 4' LONG
2. REMOVE AND REPLACE SIDEWALK, 25 SY
3. REMOVE AND REPLACE SIDEWALK, 20 SY
4. MOVE TREE TO THE SOUTH (EXACT LOCATION TBD BY UFA ARBORIST)
5. REMOVE EXISTING CROSSWALK MARKINGS
6. MOVE STOP SIGN TO THE NORTH AND ALIGN WITH STOP BAR

<b>LEGEND</b>		PCC SIDEWALK
		BRICK SIDEWALK
		GRASS
		EXISTING CONDITIONS
		PROPOSED CONDITIONS
		DETECTABLE WARNING SURFACE

**The Temple Group, Inc.**

1120 Connecticut Avenue, NW  
 Suite 310  
 Washington, DC 20036  
 Ph.: 202-822-6600  
 Fax: 202-822-6603  
 www.thetemplegroup.com

No.	DESCRIPTION	NAME	DATE
REVISIONS			

DISTRICT OF COLUMBIA DEPARTMENT OF TRANSPORTATION INFRASTRUCTURE PROJECT MANAGEMENT ADMINISTRATION	
<b>CITY-WIDE AMERICANS WITH          DISABILITIES ACT COMPLIANCE</b> DCKA-2011-C-0059	
<b>37TH AND W PL. , NW</b>	
PROJECT ENG. <u>AK</u>	DESIGN BY <u>SA</u>
CHECKED BY <u>AK</u>	DRAWN BY <u>SA</u>
FILE _____	DATE _____
SHEET 01 OF 01	
DWG NO.	