



**CONSTRUCTION NOTES:**

1. REMOVE AND REPLACE RAMP
2. REMOVE AND REPLACE RAMP WITH 5' LONG RAMP
3. NEW RAMP
4. REMOVE AND REPLACE RAMP WITH PARALLEL RAMP
5. REMOVE AND REPLACE RAMP WITH BLENDED TRANSITION
6. REPAIR AND REPLACE PCC SIDEWALK, 13' X 10'
7. REPAIR AND REPLACE PCC SIDEWALK, 12' X 11'
8. REPAIR AND REPLACE PCC SIDEWALK, 12' X 6'
9. REPAIR AND REPLACE PCC SIDEWALK, 6' X 3'
10. REMOVE AND REPLACE DRIVEWAY, 13' X 10'
11. REPAIR AND REPLACE PCC CURB, .75 CY
12. REPAIR AND REPLACE PCC SIDEWALK, 25' X 12'
13. REPAIR AND REPLACE PCC SIDEWALK, 25' X 15'
14. REPAIR AND REPLACE PCC SIDEWALK, 30' X 11'
15. REPAIR AND REPLACE PCC SIDEWALK, 17' X 9'
16. ADD FLEXI-PAVE, 12' X 3'
17. ADD FLEXI-PAVE 12' X 4'
18. REPAIR AND REPLACE PCC SIDEWALK, 14' X 7'
19. MOVE WALL BACK 9' SE AND ADD PCC SIDEWALK, 15' X 9'
20. ADD FLEXI-PAVE, 14' X 3'
21. REPAIR AND REPLACE PCC SIDEWALK, 19' X 8'
22. ADD PCC SIDEWALK, 9' X 3'
23. REMOVE CROSSWALK
24. REPLACE PAVEMENT MARKINGS
25. ADJUST MANHOLE FRAME

<b>LEGEND</b>		PCC SIDEWALK
		BRICK SIDEWALK
		GRASS
		EXISTING CONDITIONS
		PROPOSED CONDITIONS
	DETECTABLE WARNING SURFACE	

**The Temple Group, Inc.**  
 1120 Connecticut Avenue, NW  
 Suite 310  
 Washington, DC 20036  
 Ph.: 202-822-6600  
 Fax: 202-822-6603  
 www.thetemplegroup.com

No.	DESCRIPTION	NAME	DATE
REVISIONS			

DISTRICT OF COLUMBIA <b>DEPARTMENT OF TRANSPORTATION</b> INFRASTRUCTURE PROJECT MANAGEMENT ADMINISTRATION	
<b>CITY-WIDE AMERICANS WITH DISABILITIES ACT COMPLIANCE</b> DCKA-2011-C-0059	
<b>COLUMBIA RD. AT 19TH ST., NW</b> <b>BUS STOP #1001724, 1001744</b>	
PROJECT ENG. <u>AK</u> DESIGN BY <u>AK</u> CHECKED BY <u>AK</u> DRAWN BY <u>VMD</u>	FILE _____ DATE _____ SHEET 01 OF 02 DWG NO. _____