



CONSTRUCTION NOTES:

1. REMOVE AND REPLACE RAMP, TYP.
2. REMOVE AND REPLACE RAMP WITH DIRECTIONAL RAMP
3. REPLACE ASPHALT WITH PCC SIDEWALK, 37 SY
4. ADD PCC SIDEWALK, 11 SY
5. REPLACE ASPHALT WITH 4' WIDE PCC SIDEWALK, 171 SY
6. REPAIR AND REPLACE PCC SIDEWALK, 18 SY
7. REPAIR AND REPLACE PCC SIDEWALK, 90 SY
8. REMOVE STONE WALL AND STAIRS AND ADD 4' WIDE PCC SIDEWALK, 50 SY; GRADE REMAINING SOIL TO EXISTING SLOPE
9. REPAIR AND REPLACE PCC SIDEWALK, 25 SY
10. ADD PCC SIDEWALK, 7 SY
11. ADD POROUS FLEXIBLE PAVING, 10 SY

LEGEND	EXISTING CONDITIONS	PCC SIDEWALK
	PROPOSED CONDITIONS	BRICK SIDEWALK
	EXISTING TRAFFIC SIGNAL CABINET	GRASS
	EXISTING PEDESTRIAN SIGNAL	DETECTABLE WARNING SURFACE

The Temple Group, Inc.
 1120 Connecticut Avenue, NW
 Suite 310
 Washington, DC 20036
 Ph.: 202-822-6600
 Fax: 202-822-6603
 www.thetemplegroup.com

No.	DESCRIPTION	NAME	DATE
REVISIONS			

DISTRICT OF COLUMBIA
 DEPARTMENT OF TRANSPORTATION
 INFRASTRUCTURE PROJECT MANAGEMENT ADMINISTRATION

CITY-WIDE AMERICANS WITH DISABILITIES ACT COMPLIANCE
 DCKA-2011-C-0059

EASTERN AVE. AT PERRY ST., NE
 BUS STOP #1003393, 3002638

PROJECT ENG.	AK
DESIGN BY	AK
CHECKED BY	AK
DRAWN BY	VMD
FILE	
DATE	01/23/14
SHEET	01 OF 01
DWG NO.	